



**LAWN & LANDSCAPE  
CONTRACTORS**

P.O. Box 332  
Yorklyn, DE 19736  
302.239.2180

**Remainder of basins and 10 bio-retention cleaned for season**

2/27/22

Greenville Overlook HOA C/O Dave Sibert

Including: Remove trash, leaves, and debris

Clear & remove pipe and / or structure blockages to maintain flow.

Remove all weeds, invasive species, and vines from SWM facilities including. Bio-Retention areas & riprap areas.

Treat all areas with non-selective herbicides to eliminate vegetation and invasive species

Remove and dispose of minor sediment from inlets, outlets, and from any adjacent curbing areas.

Cut a six-foot-wide pathway from the spillways to the outfall structures if applicable.

Properly prune all plantings in the Bi-Retention ponds

Fix erosion of areas with fabric, seed, and biodegradable fabric

\$4800 price includes all labor, equipment, and fuel.

**\*\*\*Note- This proposal is good for a period of up to 15 days from the date on the proposal**

**\$90 per truckload of debris if removed off of property (estimated 2)**

Thank you for the consideration of this proposal. If have any questions or would like to schedule any parts of the proposal, please respond to the email or call the office 302-239-2180.

Michael E. McDonald  
McDonald Lawn and Landscape Contractors Inc.  
302-239-2180  
[mcdonaldlawn@comcast.net](mailto:mcdonaldlawn@comcast.net)

---